TUMKUR DIVISION.

ADVERTISEMENTS.

The 7th June 1888.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 25th June 1888, for restoring the Dipambudhi and Kempambudhi Tanks, Registered Nos. 93 and 94 of Kunigal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed The work should be completed by end of March 1889.

2. Every contractor tendering should offer for both the works. After the Dipambudhi channel is completed lands under Kempambudhi can be supplied with water by the Dipambudhi channel. Kempambudhi tank can then be breached and pits for earthwork excavated in tank bed.

3. An estimate for Megadi-Huliyurdurga road for Rs. 10,000 will shortly be sanctioned in the vicinity. If a good and energetic contractor takes up these tank works, he will have a chance to take up the road also.

4. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

5. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for Kempambudhi and Dipambudhi Tanks," in default of which, tenders will be rejected.

6. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

8. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities for restoring Dipambudhi and Kempambudhi Tanks of Kunigal Taluk:—

Dipambudhi Tank.				Kempambudhi Tank.			
Details.	Quantity.	Per.	Rate.	Details.	Quantity.	Per.	Rate.
Distribution Left Channel.				*Bund.*			
Earth excavation ..	2,527	C. Yd.		Earthwork	13,652	C. Yd.	
Do do	9,040	Do		New stone work ..	415	Do	
Old stone work ..	390	Do		Old stone work ..	317	Do	
Clearing jungle ..	5	E.		Grade stones ..	30	No.	
Blasting rock ..	20	C. Yd.		S. M. stones ..	2	No.	
Mile and zero stones ..	4	E.					
Furlong stones ..	21	E.					
Grade stones ..	144	E.		*Weirs.*			
Index stones ..	48	E.					
Ordinary index stones ..	72	D.		New stone work ..	15	C. Yd.	
Brick in surki	1,803	C. Ft.		Excavation ..	121	Do	
Plastering	10·72	Sq.		Brick in surki ..	2,943	C. Ft.	
New stone work ..	315	C. Yd.		Plastering	5·54	Sq.	
Excavation ..	L. S. Rs	20		Slabs	480	S. Ft.	
A new sluice 0" × 1 ..	L. S. Rs.	60					

497

The 7th June 1888.

Under para 14 of the conditions of schedule contract bond, notice is hereby given that fresh sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 25th June 1888, for restoring the Gurgadahalli Tank of Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money and be superscribed "Tender for restoring the Gurgadahalli Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for restoring Gurgadahalli Tank, Registered No. 70, Tiptur Taluk.

Items of Work.	Per.	Quantity.	Rate.	Cost.	Total.
Bund—					
Earthwork	C. Yd.	19,769			
New stone work	do	2,432			
Old stone work	do	955			
Grade stones	..	42			
Bench Mark stones	..	2			
Total	..	..			
Sluice—					
No. I. Sluice cutting and clearing ..	L. S.	30			
No. II Sluice—					
Earthwork	C. Yd.	400			
Brick in chunam	C. Ft.	591			
Concrete	do	173			
Plastering	Sqr.	2·78			
Covering slabs	S. Ft.	117			
Front and orifice stones	L. S.	3			
Gibbet stones	do	15			
Total	..	..			
Waste weirs—					
Excavation	C. Yd.	3,706			
Brick in chunam	C. Ft.	2,151			
Plastering	Sqr.	5·76			
Covering slabs	S. Ft.	291			
New stone work	C. Yd.	437			
Total	..	..			

C. T. [illegible]
Executive E